



# Helix implementation plan

HLX-04 · Version 1.0 · 2026-08-27 · Helix Test Infrastructure · submitted

---

## HLX-04 T1

| Step                           | Committed date | Evidence                      |
|--------------------------------|----------------|-------------------------------|
| I-01 Factory release           | 2026-09-30     | Release certificate           |
| I-02 Delivery and installation | 2026-11-15     | Installation record           |
| I-03 Operator training         | 2026-11-26     | Eight staff attendance record |
| I-04 Site Acceptance Test      | 2026-11-30     | Signed SAT record             |

HLX-04 §2 — The early schedule leaves commissioning margin before the 31 January 2027 RFQ deadline. The included training is on site.

## HLX-04 §3 Delivery method

HLX-04 §3.1 — Helix proposes an early factory release and a short, controlled site sequence. We will complete a pre-delivery configuration review, install the chamber and controls, train the nominated operators and witness a representative acceptance run. The earlier handover date provides planning margin, but the formal completion evidence remains the signed Site Acceptance Test record.

HLX-04 §3.2 — Before site work, the parties will confirm access, utilities, safety induction and a nominated technical contact. The supplier will record the delivered configuration and installation checks. Any open item will have an owner and planned resolution. Factory release and delivery notices are progress evidence; the acceptance milestone is the witnessed SAT identified in the dated schedule.

## HLX-04 §4 Acceptance and handover

HLX-04 §4.1 — The on-site session includes eight staff and covers controlled run setup, routine safety checks, first-line fault reporting and local data export. At SAT the team will execute a representative run, inspect the channel record and export measurements and events. The submitted target is 30 November 2026; the signed record will state the actual outcome and any outstanding matter.

HLX-04 §4.2 — The supplier will give the Institute an as-installed configuration list, operator materials, sample export and service contact route. The project team should retain these with the acceptance record for later dataset validation and maintenance. A change in local scheduling should be documented through normal project controls and does not itself change the submitted tender undertaking.

## HLX-04 §5 Readiness and handover checks

HLX-04 §5.1 — The installation team will review delivery access, safe work requirements, prepared utilities and the planned attendance of the eight operators before the site visit. The check is intended to prevent a delay between physical delivery and usable operation. A delivered crate or completed wiring is not the same as accepted performance. The supplier and Institute technical lead should jointly record any open installation item and its owner.

HLX-04 §5.2 — Training for the V60 covers bank assignment, event review and recovery after interrupted runs, routine shutdown, first-line diagnostic information and how to open a service case. The attendance record should identify participants and material used. The acceptance pack should include the as-installed configuration, completed test steps, sample raw export, event log, training record and signatures. An unresolved observation should be stated as such in the pack rather than silently treated as passed.

#### HLX-04 T3

| Control point    | Record                             | Use                               |
|------------------|------------------------------------|-----------------------------------|
| Pre-installation | Site-readiness checklist           | Coordinate access and utilities   |
| Installation     | As-installed configuration         | Identify supplied system          |
| Training         | Attendance and operator materials  | Evidence of eight-person handover |
| SAT              | Signed procedure and export sample | Evidence of accepted operation    |

---

Fictional training case; all people, organisations, products, rules and events are invented.