



Peregrine implementation plan

PRG-004 · Version 1.0 · 2026-08-24 · Peregrine Instrumentation · submitted

PRG-004 T1

Step	Committed date	Evidence
I-01 Factory release	2026-10-20	Release note
I-02 Installation	2026-12-15	Installation checklist
I-03 Operator training	2027-01-08	Eight staff attendance record
I-04 Site Acceptance Test	2027-01-10	Signed SAT record

PRG-004 §2 — All schedule dates relate to the quoted 24-position configuration; an expansion would be a separate change.

PRG-004 §3 Delivery method

PRG-004 §3.1 — Peregrine's plan concentrates site work into an installation visit, a focused operator session and a witnessed acceptance test. We will provide the laboratory with a configuration record and a sample raw-data export at handover. Scheduling assumptions are based on the submitted compact system; any later chamber expansion would require separate engineering and commercial agreement.

PRG-004 §3.2 — Before site work, the parties will confirm access, utilities, safety induction and a nominated technical contact. The supplier will record the delivered configuration and installation checks. Any open item will have an owner and planned resolution. Factory release and delivery notices are progress evidence; the acceptance milestone is the witnessed SAT identified in the dated schedule.

PRG-004 §4 Acceptance and handover

PRG-004 §4.1 — The on-site session includes eight staff and covers controlled run setup, routine safety checks, first-line fault reporting and local data export. At SAT the team will execute a representative run, inspect the channel record and export measurements and events. The submitted target is 10 January 2027; the signed record will state the actual outcome and any outstanding matter.

PRG-004 §4.2 — The supplier will give the Institute an as-installed configuration list, operator materials, sample export and service contact route. The project team should retain these with the acceptance record for later dataset validation and maintenance. A change in local scheduling should be documented through normal project controls and does not itself change the submitted tender undertaking.

PRG-004 §5 Readiness and handover checks

PRG-004 §5.1 — The installation team will review delivery access, safe work requirements, prepared utilities and the planned attendance of the eight operators before the site visit. The check is intended to prevent a delay between physical delivery and usable operation. A delivered crate or completed wiring is not the same as accepted performance. The supplier and Institute technical lead should jointly record any open installation item and its owner.

PRG-004 §5.2 — Training for the CE-24 covers batch planning, run identifiers and local export, routine shutdown, first-line diagnostic information and how to open a service case. The attendance record should identify participants and material used. The acceptance pack should include the as-installed configuration, completed test steps, sample raw export, event log, training record and signatures. An unresolved observation should be stated as such in the pack rather than silently treated as passed.

PRG-004 T3

Control point	Record	Use
Pre-installation	Site-readiness checklist	Coordinate access and utilities
Installation	As-installed configuration	Identify supplied system
Training	Attendance and operator materials	Evidence of eight-person handover
SAT	Signed procedure and export sample	Evidence of accepted operation

Fictional training case; all people, organisations, products, rules and events are invented. This is not organisational policy or Singapore procurement law.